



Ovale Installation Guide

Acoustic 3D Tiles

acoufelt
making quiet

Specifications


Product Detail

Product	Ovale 3D Tiles
Application	Wall
Composition	100% polyester
Material	FilaSorb™
Content	60% min
Size	Flatlay – 400 x 530mm
	Assembled – 400 x 220 x 100mm
Thickness	7mm +/- 10%

Technical Data


Fire Test Method	AS/ISO 9705.1, Group 1
Indoor Air Quality	SCS-EC10.3-2014 v4.0 meeting standard CDPH/EHLB Standard Method v.1.2-2017, $\leq 0.5\text{mg/m}^3$
Light Fastness	ISO 105-B02, 6-7

Fittings Included




Tile Assembly

1. Assemble each tile by folding the tab at rear and securing with screws provided.




2. Secure Z-clip only to rear of all tiles that secure to Z-Clip wall rail. Align top of clip with top of flap. Tiles that do not attach to the wall rail do not require Z- clips on rear.




Mounting Z-Clip rail to wall

3. Cut Z clip to length of wall and secure at 300mm centres. **Note:** On concrete wall, please use wall plugs. On wood or steel wall, self tapping screws can be used.




4. Subsequent rails to be mounted 1070mm apart. This is crucial for the tiles to align correctly.




Mounting tiles to rails

5. Secure z-clip on rear of tile to rail, ensuring it is level and firmly held in place.




6. Continue mounting tiles from left to right with no space in between.




Mounting consecutive tiles

7. Secure next row above by connecting slots in the tiles.
Friction alone will hold the tiles in place.



8. Continue assembling rows up the wall as required, until installation is complete





acoufelt.com